

**Addendum # 1**  
**Revised Bid Schedule**  
3-19-21

Pavement Restoration 2020-2021 Project  
City of Cornelius

Bid item description revision on the Bid Schedule. Below the revised bid item is listed. The revised Bid Schedule of Prices follows on pages 2-4 and 2-5, which includes the addition of numbers for each bid item.

Please email Kevin Oppenlander at [kevin.oppenlander@corneliusor.gov](mailto:kevin.oppenlander@corneliusor.gov) with any questions.

The following revision is made to the plans and other bid documents for this project:

<b>NO.</b>	<b>Previous Item Description</b>	<b>Revised Item Description</b>
29	Plant Replacement	Plant Replacement (Waxleaf Privet, 3 gallon)

2020-2021 PAVEMENT RESTORATION AND ADA RAMP CONSTRUCTION

BID TABULATION

PAVEMENT RESTORATION - PART A

NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
<b>MOBILIZATION, TRAFFIC CONTROL, EROSION CONTROL (00200)</b>					
1	Mobilization (00210)	LS	ALL		
2	Temporary Protection and Direction of Traffic (00225)	LS	ALL		
3	Inlet Protection	EA	10.0		
<b>ROAD WORK (00300)</b>					
4	Sawcut Asphalt	LF	180.0		
<b>BASES (00600)</b>					
5	Full Depth Reclamation Base (FDR) (00643)	SY	8,641.0		
6	Portland Cement (00643)	TON	346.0		
7	Asphalt Cement Curing Seal (00643)	TON	11.00		
<b>WEARING SURFACES (00700)</b>					
8	HMAC, Level 2, 1/2 in (00745)	TON	1,960.0		

**PAVEMENT RESTORATION TOTAL**

**ADA RAMP CONSTRUCTION - PART B**

NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
<b>MOBILIZATION, TRAFFIC CONTROL, EROSION CONTROL (00200)</b>					
9	Mobilization (00210)	LS	ALL		
10	Temporary Protection and Direction of Traffic (00225)	LS	ALL		
11	General Excavation (including hauloff)	LS	1.0		
12	Erosion Control	LS	1.0		
13	Clear and Grubb	LS	1.0		
14	Sign Relocation	EA	2.0		
15	Water Valve Can Adjustment	EA	3.0		
<b>ROAD WORK (00300)</b>					
16	Sawcut Asphalt/Concrete	FT	408.0		
17	Asphalt Paving Removal and Hauloff (ADA Ramp construction only)	SF	1,130.0		
18	Curb Removal	FT	202.0		
19	Sidewalk Removal	SF	1,531.0		
<b>WEARING SURFACES (00700)</b>					
20	HMAC, Level 2, 1/2 in (00745)	TON	24.0		
21	Concrete Walks	SF	1,689.0		
22	Concrete Curb and Gutter	FT	168.0		
23	Truncated Domes	EA	13.0		
24	Return Curb	FT	420.0		
<b>RIGHT OF WAY DEVELOPMENT AND CONTROL</b>					
25	Imported Topsoil (spread and fine graded)	CYDS	12		
26	Permanent Seeding	LS	1		
27	Bark Mulch	CYDS	6		
28	Retaining wall construction	SF	30.0		
29	Plant Replacement (Waxleaf Privet, 3 gallon)	EA	8.0		
30	Junction Box - 1730	EA	1.0		

<b>ADA RAMP TOTAL</b>	
-----------------------	--

<b>PROJECT TOTAL</b>	
----------------------	--